

Bid Document for Waterford RFP Sign and Poles

Name of Responding Firm: _____

Contact Name, Phone, E-Mail: _____

Date of Bid: _____

SIGNS – High intensity retroreflective/prismatic sheeting

Sign ID	Sign Size (width x height)	Unit Cost Estimate	Estimated Quantity	Estimated Total
P1, P2 and P3, one installed on T6 & one installed on T9 (Parking symbol)	18"x24"	\$	5	\$
P4	30"x40"	\$	1	\$
P5	30"x40"	\$	1	\$
Elizabeth St. (*New parking lot not in the Plan)	30"x40"	\$	1	\$
T1	30"x40"	\$	1	\$
T2	30"x40"	\$	1	\$
T3	30"x40"	\$	1	\$
T4	30"x40"	\$	1	\$
T5	30"x40"	\$	1	\$
T6	30"x40"	\$	1	\$
T7	30"x40"	\$	1	\$
T8	30"x40"	\$	1	\$
T9	30"x40"	\$	1	\$
T10	30"x40"	\$	1	\$
T12	30"x40"	\$	1	\$
T13	30"x40"	\$	1	\$
T14	30"x40"	\$	1	\$

D1	30"x40"	\$	1	\$
G3 & G4	72"x48"	\$	2	\$
G7	98"x71.75"	\$	1	\$
Sign Fabrication Total			25	\$

Notes:

- Background color: Dark Blue Pantone #289C
- River logo color: Blue Pantone #2925C
- Back of sign color: Dark Blue Pantone #289C
- Parking symbol color: Standard DOT green
- Font and Arrows color: White
- Font: Highway Series B with letter size of 5" upper case and 3 ¾" lower case
- We are NOT requesting a bid for sign G1 shown in the plan

BASIC ROUND BLACK POLES

Sign ID	Basic Round Pole Powder Coated Black (a) Unit Cost Estimate	Estimated Pole Quantity	Estimated Total Basic Round Pole Powder Coated Black (a)
G3 & G4	\$	4	\$
T1, T10, T14, T12, T13 & D1	\$	6	\$
Basic Round Poles Total		10	\$
<i>EXTRAS: Sign stiffeners, mounting tape and channel clamps (b)</i>	NA	NA	<i>Sign stiffeners: \$</i> <i>Tape: \$</i> <i>Clamps: \$</i>
Basic Round Poles Total PLUS EXTRAS			\$

Notes:

- (a) 12' tall, 3" diameter, basic pole package with break away anchor for soil and concrete to meet NCHRP 350 standards. Powder coat black with ball finial.
- (b) May not need if pole packages come with two sign brackets. Firm to advise Village if these elements are required.
- (c) Pole installation to be conducted by the Department of Public Works and Village is responsible for all costs associated with the installation.

DECORATIVE POLES

Sign ID	Decorative Powder Coated Black Pole Package (b)	Estimated Pole Quantity	Estimated Total Decorative Powder Coated Black Pole Package (b)
P1, P2 and P3	\$	3	\$

T2, T3, T4, T5, T6, T7, T8, T9, P4, P5 & New Eliz. St. Pkng. Lot (Note: Two poles also have an additional parking symbol sign installed)	\$	11	\$
Decorative Poles Total		14	\$
<i>EXTRAS: Sign stiffeners, mounting tape and channel clamps (b)</i>	NA	NA	<i>Sign stiffeners: \$</i> <i>Tape: \$</i> <i>Clamps: \$</i>
Decorative Poles Total PLUS EXTRAS			\$

Notes:

- (a) 12' tall, 3" diameter decorative package for concrete includes: ball finial, brackets, fluted pole, with base plate, slip over base, break away anchor for soil or concrete to meet NCHRP 350 standards.
- (b) *May not need if pole packages come with two sign brackets. Firm to advise Village if these elements are required.*
- (c) Pole installation to be conducted by the Department of Public Works and Village is responsible for all costs associated with the installation.

SUMMARY OF COSTS

	Estimated GRAND TOTAL
Signs	\$
Basic Poles	\$
Decorative Poles	\$
TOTAL COST	\$
TOTAL COST WITH EXTRAS (a)	\$

Note:

- (a) May not need if pole packages come with two sign brackets. Firm to advise Village if these elements are required.
- (b) Sign G7 to be installed on existing brackets. See attached photo to see existing brackets and existing sign dimensions.

Existing Sign to be replaced with sign G7. New sign G7 to be installed on existing brackets.

